

COUNTY OF MENDOCINO
DEPARTMENT OF TRANSPORTATION
NOTICE TO BIDDERS

CONTRACT NO. 190092

Sealed proposals will be received by the Mendocino County Department of Transportation, State of California, until the hour of 2:00 o'clock P.M., April 23, 2020, at which time they will be publicly opened and read aloud in the office of the Mendocino County Department of Transportation, 340 Lake Mendocino Drive, Ukiah, California 95482 (Telephone (707) 463-4363) for construction in accordance with the Plans and Specifications to which special reference is made as follows:

COUNTY OF MENDOCINO, DEPARTMENT OF TRANSPORTATION

DOT CONTRACT NO.: 190092

2017 FIRE DAMAGE REPAIRS ON TOMKI ROAD, CR 237D IN REDWOOD VALLEY

DOT PROJECT NO.: 3030-F-1806.506

AND

2017 FIRE DAMAGE REPAIRS ON REDWOOD VALLEY ROADS

INEZ WAY, CR 237F

RANCHERIA ROAD, CR 237A

MOUNTAIN VIEW LANE, CR237H

ROAD J, CR 235

ROAD I, CR 234

MOHAWK TRAIL, CR 237G

DOT PROJECT NO.: 3030-F-1806.507

Plans, forms of proposal, contract and contract documents may be seen at the office of the County of Mendocino Department of Transportation, 340 Lake Mendocino Drive, Ukiah, California (Telephone (707) 463-4363).

PLANS AND CONTRACT DOCUMENTS MAY BE OBTAINED AT THE OFFICE OF THE COUNTY OF MENDOCINO DEPARTMENT OF TRANSPORTATION, 340 Lake Mendocino Drive, Ukiah, California 95482, upon payment of \$40.00 in company check, money order or the exact amount in cash. Please make a check or money order payable to COUNTY OF MENDOCINO. This payment is not refundable.

For this contract, the County has included a Disadvantaged Business Enterprises (DBE) goal of **12** percent. Bidders need not achieve the percentage stated as a condition of award.

~~This project is subject to the "Buy America" provisions of the surface transportation assistance act of 1982 as amended by the Intermodal Surface Transportation Efficiency Act of 1991.~~

No pre-bid meeting is scheduled for this project.

Bids are required for the entire work described herein.

The prime Contractor for the work herein shall possess the following valid State of California licenses:

“A” - General Engineering or C-12 Earthwork and Paving at the time this Contract is awarded.

Pursuant to Section 1771.1(a) of the Labor Code of the State of California, A contractor or subcontractor shall not be qualified to bid on, be listed in a bid proposal, subject to the requirements of Section 4104 of the Public Contract Code, or engage in the performance of any contract for public work, as defined in this chapter, unless currently registered and qualified to perform public work pursuant to Section 1725.5. It is not a violation of this section for an unregistered contractor to submit a bid that is authorized by Section 7029.1 of the Business and Professions Code or by Section 10164 or 20103.5 of the Public Contract Code, provided the contractor is registered to perform public work pursuant to Section 1725.5 at the time the contract is awarded.

If the successful low bidder has a physical place of business in unincorporated Mendocino County, they will be required to obtain a County Business License prior to Notice to Proceed.

BID ITEM LIST SCHEDULE 1

FDR-Cement, Tomki Road, County Road 237D, Redwood Valley				
MCDOT PROJECT NO.: 3030-F-1806.506				
<u>ITEM NO.</u>	<u>ITEM CODE</u>	<u>ITEM DESCRIPTION</u>	<u>UNIT CODE</u>	<u>ESTIMATED QUANTITY</u>
1	100100	DEVELOP WATER SUPPLY	LS	1
2	120090	CONSTRUCTION AREA SIGNS	LS	1
3	120100	TRAFFIC CONTROL SYSTEM	LS	1
4	130200	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	1
MILE POST 0.00 TO 2.21 & MILE POST 2.43 TO 2.50 (39.312862, -123.220047 TO 39.342862, -123.227714 AND 39.345505, -123.229172 TO 39.346539, -123.229187)				
5	304000	FULL-DEPTH RECLAMATION (6" DEPTH)	SQYD	29450.7
6	304300	ASPHALTIC EMULSION (FDR, 0.13 - 0.25 gal/sqyd)	TON	30.7
7	304100	CEMENT (FDR)	TON	742.2
8	304400	MIX DESIGN (FDR)	LS	1
MILE POST 3.80 TO MILE POST 4.75 (39.364307, -123.233032 TO 39.376019, -123.233253)				
9	304000	FULL-DEPTH RECLAMATION (6" DEPTH)	SQYD	12261.3
10	304300	ASPHALTIC EMULSION (FDR, 0.13 - 0.25 gal/sqyd)	TON	12.8
11	304100	CEMENT (FDR)	TON	309
12	304400	MIX DESIGN (FDR)	LS	1
ALL TREATED ROAD SEGMENTS				
13	370001	SAND COVER (1.0-2.0 lbs/sqyd)	TON	41.7
14	374493	POLYMER ASPHALTIC EMULSION (chip seal, .30-.45 gal/sqyd)	TON	78.2
15	375001	SCREENINGS 3/8" (chip seal, 23-30 lbs/sqyd)	SQYD	41712
16	374493	POLYMER ASPHALTIC EMULSION (chip seal, .20-.30 gal/sqyd)	TON	52.1
17	375001	SCREENINGS 5/16" (chip seal, 12-20 lbs/sqyd)	SQYD	41712
18	840656	PAINT TRAFFIC STRIPE, YELLOW 4" (2 COATS)	LF	17064
19	840666	PAINT PAVEMENT MARKING (2 COATS)	SQFT	99
20	999990	MOBILIZATION	LS	1

BID ITEM LIST SCHEDULE 2

FDR-Cement, 2017 Fire Damage Repairs on Redwood Valley Roads MCDOT PROJECT NO.: 3030-F-1806.507				
<u>ITEM NO.</u>	<u>ITEM CODE</u>	<u>ITEM DESCRIPTION</u>	<u>UNIT CODE</u>	<u>ESTIMATED QUANTITY</u>
1	999990	MOBILIZATION	LS	1
2	100100	DEVELOP WATER SUPPLY	LS	1
3	120090	CONSTRUCTION AREA SIGNS	LS	1
4	120100	TRAFFIC CONTROL SYSTEM	LS	1
5	130200	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	1
Road I, County Road 234, Mile Post 0.17 to Mile Post 0.61, 6" Full-Depth Reclamation with Double Chip Seal Surface				
6	304000	FULL-DEPTH RECLAMATION (6" DEPTH)	SQYD	5168.89
7	304100	CEMENT (FDR)	TON	130.3
8	304300	ASPHALTIC EMULSION (FDR, 0.13 - 0.25 gal/sqyd)	TON	5.4
9	304400	MIX DESIGN (FDR)	LS	1
10	370001	SAND COVER (1.0-2.0 lbs/sqyd)	TON	5.2
11	374493	POLYMER ASPHALTIC EMULSION (chip seal, .30-.45 gal/sqyd)	TON	9.7
12	375001	SCREENINGS 3/8" (chip seal, 23-30 lbs/sqyd)	SQYD	5168.89
13	374493	POLYMER ASPHALTIC EMULSION (chip seal, .20-.30 gal/sqyd)	TON	6.5
13	375001	SCREENINGS 5/16" (chip seal, 12-20 lbs/sqyd)	SQYD	5168.89
15	840656	PAINT TRAFFIC STRIPE, YELLOW 4" (2 COATS)	LF	2326
Road I, County Road 234, at Mile Post 0.90, 6" Full-Depth Reclamation with Double Chip Seal Surface				
16	304000	FULL-DEPTH RECLAMATION (6" DEPTH)	SQYD	171.11
17	304100	CEMENT (FDR)	TON	4.3
18	304300	ASPHALTIC EMULSION (FDR, 0.13 - 0.25 gal/sqyd)	TON	0.1
19	304400	MIX DESIGN (FDR)	LS	1
20	370001	SAND COVER (1.0-2.0 lbs/sqyd)	TON	0.2
21	374493	POLYMER ASPHALTIC EMULSION (chip seal, .30-.45 gal/sqyd)	TON	0.3
22	375001	SCREENINGS 3/8" (chip seal, 23-30 lbs/sqyd)	SQYD	171.11
23	374493	POLYMER ASPHALTIC EMULSION (chip seal, .20-.30 gal/sqyd)	TON	0.2
24	375001	SCREENINGS 5/16" (chip seal, 12-20 lbs/sqyd)	SQYD	171.11
Road J, County Road 235, Mile Post 0.00 to end of County Road, 6" Full-Depth Reclamation with Double Chip Seal Surface				
25	304000	FULL-DEPTH RECLAMATION (6" DEPTH)	SQYD	10560
26	304100	CEMENT (FDR)	TON	266.1
27	304300	ASPHALTIC EMULSION (FDR, 0.13 - 0.25 gal/sqyd)	TON	5.5
28	304400	MIX DESIGN (FDR)	LS	1
29	370001	SAND COVER (1.0-2.0 lbs/sqyd)	TON	10.6
30	374493	POLYMER ASPHALTIC EMULSION (chip seal, .30-.45 gal/sqyd)	TON	19.8
31	375001	SCREENINGS 3/8" (chip seal, 23-30 lbs/sqyd)	SQYD	10560
32	374493	POLYMER ASPHALTIC EMULSION (chip seal, .20-.30 gal/sqyd)	TON	13.2
33	375001	SCREENINGS 5/16" (chip seal, 12-20 lbs/sqyd)	SQYD	10560
34	840656	PAINT TRAFFIC STRIPE, YELLOW 4" (2 COATS)	LF	1752
35	840666	PAINT PAVEMENT MARKINGS (2 COATS)	SQFT	40

Rancheria Road, CR 237A, Mile Post 0.00 to end of County Road				
6" Full-Depth Reclamation with Double Chip Seal Surface				
36	304000	FULL-DEPTH RECLAMATION (6" DEPTH)	SQYD	4177.78
37	304100	CEMENT (FDR)	TON	105.3
38	304300	ASPHALTIC EMULSION (FDR, 0.13 - 0.25 gal/sqyd)	TON	2.2
39	304400	MIX DESIGN (FDR)	LS	1
40	370001	SAND COVER (1.0-2.0 lbs/sqyd)	TON	4.2
41	374493	POLYMER ASPHALTIC EMULSION (chip seal, .30-.45 gal/sqyd)	TON	7.8
42	375001	SCREENINGS 3/8" (chip seal, 23-30 lbs/sqyd)	SQYD	4177.78
43	374493	POLYMER ASPHALTIC EMULSION (chip seal, .20-.30 gal/sqyd)	TON	5.2
44	375001	SCREENINGS 5/16" (chip seal, 12-20 lbs/sqyd)	SQYD	4177.78
45	840656	PAINT TRAFFIC STRIPE, YELLOW 4" (2 COATS)	LF	1868
46	840666	PAINT PAVEMENT MARKINGS (2 COATS)	SQFT	40
Mohawk Trail, CR 237G, Mile Post 0.00 to end of County Road				
6" Full-Depth Reclamation with Double Chip Seal Surface				
47	304000	FULL-DEPTH RECLAMATION (6" DEPTH)	SQYD	863.33
48	304100	CEMENT (FDR)	TON	21.8
49	304300	ASPHALTIC EMULSION (FDR, 0.13 - 0.25 gal/sqyd)	TON	0.4
50	304400	MIX DESIGN (FDR)	LS	1
51	370001	SAND COVER (1.0-2.0 lbs/sqyd)	TON	0.9
52	374493	POLYMER ASPHALTIC EMULSION (chip seal, .30-.45 gal/sqyd)	TON	1.6
53	375001	SCREENINGS 3/8" (chip seal, 23-30 lbs/sqyd)	SQYD	863.33
54	374493	POLYMER ASPHALTIC EMULSION (chip seal, .20-.30 gal/sqyd)	TON	1.1
55	375001	SCREENINGS 5/16" (chip seal, 12-20 lbs/sqyd)	SQYD	863.33
56	840666	PAINT PAVEMENT MARKINGS (2 COATS)	SQFT	40
Inez Way, County Road 237F, Mile Post 0.00 to end of County Road				
Replace 6" Base, Double Chip Seal first 80 x 20 feet of Surface				
57	280200	REPLACE BASE	CY	129.69
58	260203	CLASS 2 AGGREGATE BASE (3/4")	CY	129.69
59	374493	POLYMER ASPHALTIC EMULSION (chip seal, .30-.45 gal/sqyd)	TON	0.3
60	375001	SCREENINGS 3/8" (chip seal, 23-30 lbs/sqyd)	SQYD	177.78
61	374493	POLYMER ASPHALTIC EMULSION (chip seal, .20-.30 gal/sqyd)	TON	0.2
62	375001	SCREENINGS 5/16" (chip seal, 12-20 lbs/sqyd)	SQYD	177.78
63	840666	PAINT PAVEMENT MARKINGS (2 COATS)	SQFT	40
Mountain View Lane, County Road 237H, Mile Post 0.00 to end of County Road				
Replace 6" Base, Double Chip Seal first 80 x 20 feet of Surface				
64	280200	REPLACE BASE	CY	183.8
65	260203	CLASS 2 AGGREGATE BASE (3/4")	CY	183.8
66	374493	POLYMER ASPHALTIC EMULSION (chip seal, .30-.45 gal/sqyd)	TON	0.3
67	375001	SCREENINGS 3/8" (chip seal, 23-30 lbs/sqyd)	SQYD	177.78
68	374493	POLYMER ASPHALTIC EMULSION (chip seal, .20-.30 gal/sqyd)	TON	0.2
69	375001	SCREENINGS 5/16" (chip seal, 12-20 lbs/sqyd)	SQYD	177.78
70	840666	PAINT PAVEMENT MARKINGS (2 COATS)	SQFT	40

The County of Mendocino hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement, Disadvantaged Business Enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration of the award.

Pursuant to the provisions in Section 1773 of the Labor Code of the State of California, the Board of Supervisors of the County of Mendocino has obtained from the Director of the Department of Industrial Relations the general prevailing rate of wages, and the schedule of employer payments for health and welfare, vacation, pension and similar purposes in the County. Interested parties may review these wage rates and schedules at the Department of Transportation, 340 Lake Mendocino Drive, Ukiah, California. The successful Contractor shall obtain a copy of prevailing wage rates from the Engineer and shall post same at a prominent place at the job site.

For this contract the general prevailing rate of wages as ascertained by County shall be those in effect on the bid date. Future effective wage rates, which have been predetermined and are on file with the Department of Industrial Relations, are referenced in the published wage rates of the Director of the Department of Industrial Relations.

The County of Mendocino reserves the right to reject any and all bids or to waive any defects or irregularity in bidding.

Dated 4/2/2020

Howard N. Dashiell
Director of Transportation of the
County of Mendocino,
State of California

BY: 

Director